

KANSAS

FORM CP-3
Rev. 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-079-20425-0000

245 North Water
Wichita, KS 67202

Operator's Full Name Phillips Petroleum Company

Complete Address Box 287, Great Bend, Ks. 67530

Lease Name Schlender "A" Well No. # 1

Location C. NW. SW. Sec. 10 Twp. 22-S Rge. 2 (~~East~~) (West)

County Harvey Total Depth 3285'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Ks. 67524 License No. # 683

Operation Completed: Hour: 1:40 PM Day: 31 Month: 12 Year: 19 80

The above well was plugged as follows:

8 5/8" sur. csg. 305' circ./cent. 4 1/2" csg. 3283'/285 sx. cent.

PBTD 3173', Perf. 3144' to 48', 3158' to 66'.

Halliburton Services pumped 35 sx. 50-50-Posmix cent. 6% gel down 4 1/2"

Pump Press 1000# SIP 800# SLM 2689'

Shot & pulled 2130' 4 1/2" csg. Left 1153' csg. in hole.

Halliburton Services pumped 3 sx hulls, 20 sx. salt gel, 120 sx. Posmix

cent. 6% gel down 8 5/8" csg. SIP 450#

RECEIVED
STATE CORPORATION COMMISSION
1-6-81
JAN 6 1981

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

DATE 1-8-81

Signed: Don Thompson
Conservation Division Agent

INV. NO. 8383-E

INVOICED