

Form CP-3  
Rev. 6-26-62KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUL 1 1963

CONSERVATION DIVISION  
Wichita, KansasJ. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, KansasOperator's Full Name Sunray DX Oil Co.Complete Address: 321 W. Douglas, Wichita, KansasLease Name Dan Eway Well No. # 4Location C SE NW Sec. 17 Twp. 22 Rge. 22 (E) (W) WCounty Hodgeman Total Depth 4537Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XOther well as hereafter indicated:     Plugging Contractor: Forbes Casing Pulling Co.Address: Box 221, Great Bend, Kansas License No. 49Operation Completed: Hour 11:00AM Day 24th Month June Year 1963

The Above well was plugged as follows:

249' of 8 5/8" surface pipe, cement circulated with 225 sacks. 4511' of  
5 1/2" long string, cemented with 125 sacks. Plugged back to 4524'. Top  
perferation 4130'. Sanded to 4120', cemented with 5 sacks. Fluid level  
in hole was at 240', plug was set at 240', 10' rock bridge, cemented  
with 4 sacks and let set over night. Next morning 16 sacks were added  
to plug. Hole was filled with mud to 40'. 10' rock bridge, cemented  
with 10 sacks to base cellar.

3615' of 5 1/2" long string recovered from hole

I hereby certify that the above well was plugged as herein stated.

Signed: Audie Elving  
Well Plugging Supervisor