

*80*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

OCT 9 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Rains-Williamson Oil Company

Complete Address: 412 Union Center, Wichita, Kansas

Lease Name Ewy Well No. B-3

Location SW NE Sec. 17 Twp. 22S Rge. 22 (E) (W)

County Hodgeman Total Depth 4532'

Abandoned Oil Well x Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casine Pulling Service.

Address: Chase, Kansas License No. 436

Operation Completed: Hour 7 PM Day 7 Month 10 Year 63

The Above well was plugged as follows:

8 5/8" - 257' Circulated w/cement. 4 1/2" - 4530' Cemented.

Plug bottom w/sand 4532' to 4520' 5 Sax.cement 4520' to 4470'

Mud 4470' to 700' 25 Sax.cement 700' to 625'

Mud 625' to 250' 25 Sax.cement 250' to 175'

Mud 175' to 50' 10' Rock bridge 50' to 40'

15 Sax.cement 40' to surface. Weld cap on surface.

Company Pump. Pulled 3695' 4 1/2" Pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/10/63  
INV. NO. 7864-u

Signed: *Hugh Scott*  
Well Plugging Supervisor