



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 21 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Braden-Deem
 Complete Address 200 East 1st., Wichita, Kansas 67202
 Lease Name Ewy "B" Well No. 2
 Location SE NE Sec. 17 Twp. 22 Rge. 22 (SE) (W)
 County Hodgeman Total Depth 4518'
 Abandoned Oil Well X Gas Well Input Well SWD Well D & A
 Other well as hereafter indicated
 Plugging Contractor Pipe Pullers Inc.
 Address Great Bend, Kansas License No. 462'
 Operation Completed: Hour 2:00Pm Day 13 Month 8 Year 1974

The above well was plugged as follows:

8 5/8" to 283' circulated w/ cement.	5 1/2" to 4511' cemented.
7' of open hole.	Plug bottom w/ sand & 5 sacks cement.
Top of cement 4450'	Mud 4450' to 800'
Spotted 80 sacks cement 800' to 500'	Mud 500' to 250'
Spotted 30 sacks cement 250' to 150'	Mud 150' to 40'
Plug, hulls & 16 sacks cement 40' to 0'.	Allied Pump
Pulled 3400' of 5 1/2" casing.	

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/22/74
INV. NO. 9749-W

Signed: Edgar J. Lucas
Well Plugging Supervisor