

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- ^{18, 188-21-413-0000} Abandoned

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Oil Properties Management Inc

Complete Address 221 N Maine Suite 200, Wichita Ks

Lease Name Soden-Cornwell Well No. 1

Location NW SW NE Sec. 18 Twp. 23 Rge. 12 (East) (West)

County St. Francis Total Depth 3915'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Nicholas Coating

Address Box 373 Geneva Ks. License No. 711

Operation Completed: Hour: 2:30 pm Day: 1 Month: April Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

4 1/2 casing set at 3910. Sand back to 3800, 4 SK Cement with Baker Recovered 2995' of 4 1/2. Squeezed well with 5 Halls 25 SK gel, 140 SK Cement, 50, 50 poz 49 gel 39 cal, max pres. 350# Shut in 250#

Created by Halbach

Amount of Surface Casing: 8 1/2 set at 295' with 225 SK Cement 39 cc

I hereby certify that the above plugging instructions were given as herein stated.

Signed: J. A. [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

4-6-82

RECEIVED
STATE CORPORATION COMMISSION

APR - 6 1982

Signed: _____
CONSERVATION DIVISION
Conservation Divisions Agent

INVOICED
DATE 4-6-82
INV. NO. 9875-W