

15-055-10203-0000

Form GP-3

Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 9 1964

03-09-64

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Kansas Nebraska Natural Gas Co. Inc.

Complete Address: Box 608 Hasting, Nebraska

Lease Name Wilson Well No. B-1

Location C NE Sec. 33 Twp. 27 Rge. (E) (W) 33

County Finney Total Depth 2652'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: C.L. Hinds

Address: Liberal, Kansas License No. 302

Operation Completed: Hour 7 PM Day 5 Month 3 Year 64

The Above well was plugged as follows:

8 5/8"-302' Circulated w/cement. 5 1/2"-2652' Cemented.

Plug back to 2636' Perforations 2609'

Plug bottom w/rock and 20 Sax.cement 2636' to 2430' Mud 2430' to 700'

25 Sax.cement 700' to 625' Mud 625' to 300'

25 Sax.cement 300' to 225' Mud 225' to 40'

Plug, Hulls, 15 Sax.cement 40' to 0

Company Pump. Pulled 1438' 5 1/2" Pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 3/10/64
INV. NO. 8754-W