

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-055-00033-
0000

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

JAN 3 1968

01-03-68

Operator's Full Name Eureka Drilling Co.

Complete Address: Hamilton, Kansas

Lease Name Wampler "A" Well No. 1

Location C SE SE Sec. 17 Twp. 21 Rge. 33 ~~(E)~~ (W)

County Finney Total Depth 4695'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 4:30PM Day 31 Month 12 Year 1967

The Above well was plugged as follows:

8 5/8" to 240' circulated w/ cement. 5 1/2" to 4692' cemented.

Top perforations 4189' Plug bottom w/ 30 sacks cement

Top of cement 3800' Mud 3800' to 600'

Spotted 40 sacks cement 600' to 470' Mud 470' to 240'

Spotted 25 sacks cement 240' to 140' Mud 140' to 40'

Plug, Hulls & 10 sacks cement 40' to 0' Company Pump

Pulled 2002' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edmund J. Eaves
Well Plugging Supervisor

DATE 1-3-68

INV. NO. 7037-W