

KANSAS

15-055-10087-0000

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 30 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Cities Service Oil Co
Complete Address Box 1098, Liberal, Kansas 67901
Lease Name Wampler "A" Well No. 2
Location C NE SE Sec. 17 Twp. 21 Rge. 33 (E) (W)
County Finney Total Depth 4700'
Abandoned Oil Well Gas Well X Input Well SWD Well D & A X
Other well as hereafter indicated None
Plugging Contractor Sargent Casing Pulling Co
Address Box 506, Liberal., Kansas License No. 511
Operation Completed: Hour 11:30AM Day 27 Month 11 Year 1970

The above well was plugged as follows:

8 5/8" to 264' circulated w/ cement. 4 1/2" to 2716' cemented.
Top perforations 2519' Plug bottom w/ 20 sacks cement.
Top of cement. 2355' Mud 2355' to 750'
Spotted 25 sacks cement 750' to 650' Mud 650' to 260'
Spotted 25 sacks cement 260' to 160' Mud 160' to 45'
Plug. Halls & 15 sacks cement 45' to 0'. Company Pump
Pulled 1510' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edwin J. Evers
Well Plugging Supervisor

INVOICED
DATE 12/1/70
INV. NO. 2945-W