

15-185-19373-0001

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 25 1965

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Santa Fe Pipe & Supply Inc.

Complete Address: P. O. Box 562, Great Bend, Kansas

Lease Name McCune Well No. # 1

Location SE NW NE Sec. 35 Twp. 22 Rge. 12 (E) (W)W

County Stafford Total Depth 3695'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Santa Fe Pipe & Supply Inc.

Address: P. O. Box 562, Great Bend, Kansas License No. 574

Operation Completed: Hour 11:00AM Day 22nd Month Jan. Year 1965

The Above well was plugged as follows:

241' of 8 5/8" surface pipe, cemented with 210 sacks. 3694' of 4 1/2" long
string, cemented with 125 sacks. Bottom of the hole was sanded to 3680',
and cemented with 3 sacks. 2790' of 4 1/2" long string was recovered from
the hole. Fluid was up in the hole. Bridge plug was pushed in fluid to
240', and 10' of rock bridge on plug. 5 sacks of cement was mixed in
barrel and put on plug at 230', through the dump bailer. And let set
over-night, Next morning hole bailed down, and 20 sacks of cement was
added to plug. Hole was filled with mud to 40', 10' of rock bridge, and
cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 1/26/65

INV. NO. 580-W