



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
JUL 7 1970  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Glenn \_\_\_\_\_ of Cities Service Oil \_\_\_\_\_ has this  
date requested permission to plug the following described well:

Mr. Glenn \_\_\_\_\_ guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Co.

Complete Address: Box 308, Great Bend, Kansas

Lease Name: Hann "A" Well No. 1

Location: SW NW NE Sec. 26 Twp. 22 Rge. 22 ~~(E)~~ (W)

County: Hodgeman Total Depth 4409' Oil Well X

Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X Lost Hole \_\_\_\_\_

Mr. Glenn \_\_\_\_\_ was instructed to plug the well as follows:

8 5/8" to 249' circulated w/ cement. 5 1/2" to 4393' cement.ed

Open hole 4409' to 4393' Plug bottom w/ sand & 5 sacks cement.

Top of cement. 4300' Mud 4300' to 850'

Spot 80 sacks cement 850' to 550' Mud 550' to 240'

Spot 30 sacks cement 240' to 140' Mud 140' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

Conservation Division Agent