



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 7 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Glenn of Cities Service Oil Co. has this date requested permission to plug the following described well:

Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Co.

Complete Address: Box 308, Great Bend, Kansas

Lease Name: Hertel Well No. 1

Location: C NE SW Sec. 26 Twp. 22 Rge. 22 (E) (W)

County: Hodgeman Total Depth 4417' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Glenn was instructed to plug the well as follows:

8 5/8" to 347' circulated w/ cement. 5 1/2" to 4409' cemented.

Open Hole to 4417' Plug bottom w/ sand & 5 sacks cement

Top of cement 4350' Mud 4350' to 3850'

Spot 80 sacks cement 850' to 550' Mud 550' to 340'

Spot 30 sacks cement 340' to 240' Mud 240' to 40'

Plug, Halls & 10 sacks cement 40' to 0',

Very truly yours,

Conservation Division Agent