



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

SEP 24 1964

CONSERVATION DIVISION
Wichita, Kansas

15-185-19369-0000

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Harold Boyd of A. L. Jackson Drilling Co. has this date requested permission to plug the following described well:

Mr. Boyd guarantees payment of the plugging fee.

Operator's full Name: E. H. Riggs

Complete Address: 1107 Union National Bldg., Wichita, Kans.

Lease Name: Spangenberg Well No. # 2

Location: SW NW NE Sec. 4 Twp. 23 Rge. 12 (E) (W) W

County Stafford Total Depth 3734 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Boyd was instructed to plug the well as follows:

265' of 8 5/8" surface pipe, cement circulated. Fill hole with drilling mud to 240', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving