



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 28 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Glenn of Specter has this

date requested permission to plug the following described well:

Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: Specter Pipe & Supply Incl

Complete Address: Box 169, Russell, Kansas

Lease Name: Miller Estate Well No. 5

Location: C SE NE Sec. 8 Twp. 22 Rge. 22 (E) (W)

County: Hodgeman Total Depth 4580' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Glenn was instructed to plug the well as follows:

8 5/8" to 255' circulated w/ cement. 5 1/2" to 4580' cemented.

No Perforations Set Plug at 3800'

Mud 3800' to 800' Spot 80 sacks cement 800' to 500'

Mud 500' to 250' Spot 30 sacks cement 250' to 150'

Mud 150' to 40' Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

Edward J. Eves  
Conservation Division Agent