



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

RECEIVED  
STATE CORPORATION COMMISSION

JUN 28 1973

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agency)

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Glenn of Specter has this

date requested permission to plug the following described well:

Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: Specter Pipe & Supply

Complete Address: Box 169, Russell, Kansas

Lease Name: Miller Estate Well No. 4

Location: C NE NE Sec. 8 Twp. 22 Rge. 22 (E) (W) XX

County: Hodgeman Total Depth 4575' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Glenn was instructed to plug the well as follows:

8 5/8" to 260' circulated w/ cement. 5 1/2" to 4574' cemented.

Top perforations 4480'. Plug bottom w/ sand & 5 sacks cement to 4080'

Mud 4080' to 800' Spott 80 sacks cement 800' to 500'

Mud 500' to 250' Spott 30 sacks cement 250' to 150'

Mud 150' to 40' Plug, Hulls & 10 sacks cement 40' to 0.

Very truly yours,

*Edgar J. Evers*  
Conservation Division Agent