



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

RECEIVED
STATE CORPORATION COMMISSION

JUL 20 1973

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Glenn of Specter has this
date requested permission to plug the following described well:

Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: Specter Pipe & Supply Inc.

Complete Address: Box 169, Russell, Kansas

Lease Name: Miller Estate Well No. 2

Location: C NW SE Sec. 8 Twp. 22 Rge. 22 (E) (W)

County: Hodgeman Total Depth 4547' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Glenn was instructed to plug the well as follows:

8 5/8" to 250' circulated w/ cement. 5 1/2" to 4540' cemented.

7' of open hole Plug bottom w/ sand & 5 sacks cement.

Top of cement 4450' Mud 4450' to 400'

Spot 120 sacks cement 400' to 0'.

Very truly yours,

Conservation Division Agent