



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED STATE CORPORATION COMMISSION MAY 9 - 1974 CONSERVATION DIVISION Wichita, Kansas

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. Swope of Phillips has this

date requested permission to plug the following described well:

Mr. Swope guarantees payment of the plugging fee.

Operator's full Name: Phillips Petroleum Co.

Complete Address: Box 287, Great Bend, Kansas

Lease Name: Dimmick AB Well No. 1

Location: 660' FEL & 660' FNL Sec. 1 Twp. 22 Rge. 22 (E) (W)

County: Hodgeman Total Depth 4480' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Swope was instructed to plug the well as follows:

- 8 5/8" to 427' circulated w/ cement. Spot 75 sacks cement 4480' to 4219'
Mud 4219' to 1020' Spot 110 sacks cement 1020' to 637'
Mud 637' to 475' Spot 50 sacks cement 475' to 301'
Mud 301' to 45' Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

[Signature] Conservation Division Agent