



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 07 1982  
CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Ron Berton of Empire Oil Operations has this date requested permission to plug the following described well:

Operator's Full Name: High Plains Oil Exploration

Complete Address: 25th & Vine, Hays, Mo. 67601 # 6171

Lease Name: Cure Well No. 1

Location: C-NE SE Sec. 23 Twp. 22 Rge. 21 (E) (W)

County: Hodgman Total Depth: 4635

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Berton was instructed to plug the well as follows:

8 5/8" - 367' SP, cas. w/ 200 sacks common - 2% Gel. - 3% lb. Cl.

Ordered 160 sacks 50 pos mix - 4% Gel. - 3% lb. Cl. + 8 5/8" plug. spot w/ drill stem w/ heavy mud between all plugs. 1st plug C 990' w/ 100 sacks

2nd plug C 400' w/ 40 sacks

3rd plug - solid bridge of hulls & plug C 40' w/ 10 sacks

Circulate 10 sacks in rat hole.

Very truly yours,

[Signature]  
Conservation Division Agent