



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. - 212 N. Market
 WICHITA, KANSAS 67202

RECEIVED
 MAR 25 1968
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

March 18, 1968

Dear Sir:

Mr. Buck Smith of Glen & Smith Pipe Pulling Co. has this date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Bea Drilling Co., Inc.

Complete Address: Box 247 Ellinwood, Kansas.

Lease Name: Darr Well No. #1

Location: SW-SW-SW Sec. 18 Twp. 22 Rge. 11 (E) (W) W

County: Stafford Total Depth 3665' Oil Well

Gas Well Input Well SWD Well X D & A Lost Hole

Mr. Smith was instructed to plug the well as follows:

267' of 8 5/8" surface pipe circulated with 165 sacks cement.

4 1/2" long string set at 3657'. Rock from 3110' to 3096',

dumped 3 sacks cement. Set plug at 2805' & 2 sacks cement.

Squeezed hole in casing at 267'. Drilled out cement to 400'

Pumped 10 sacks mud & 40 sacks cement at 600 lbs. pressure. Cement to surface.

Very truly yours,

[Signature]
 Conservation Division Agent