

R


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Harvey County, Sec. 36 Twp. 22S Rge. (E) 3 (W)  
Location as "NE/CNW/SW" or footage from lines C SW NW NW  
Lease Owner Donald T. Ingling, et al.  
Lease Name Willow Lake Well No. 1  
Office Address 615 First National Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 20 1968  
Application for plugging filed Verbal Approval 19  
Application for plugging approved Verbal Approval 19  
Plugging commenced December 20 1968  
Plugging completed December 20 1968  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh E. Scott  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	250'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud from 3,795 feet (rotary total depth) to 250 feet. Set bottom plug at 250 feet and cemented with 25 sacks cement. Filled hole with heavy rotary mud to 40 feet. Set plug at 40 feet and cemented with 10 sacks cement, 2 sacks cement in rathole.

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 27 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, INC.  
Address 200 N. Main, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Arlo B. Romer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arlo B. Romer  
200 N. Main, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of December, 1968

Martha Hartperce  
Martha Hartperce Notary Public.

My commission expires April 21, 1971

KANSAS GEOLOGICAL SOCIETY  
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
KANSAS GEOLOGICAL SOCIETY BUILDING  
508 EAST MURDOCK - WICHITA, KANSAS

R

COMPANY Donald T. Ingling, et al

SEC. 36 T. 22S R. 3W  
LOC. C SW NW NW

FARM Willow Lake NO. 1

COUNTY Harvey

TOTAL DEPTH 3,795'


COMM. December 4, 1968

COMP. December 20, 1968

SHOT OR TREATED

CONTRACTOR H-30, INC.

ISSUED



CASING

20 10  
15 8-5/8" 250' cemented w/175 sx cement ELEVATION 1428 KB  
12 6  
13 5

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

		SAMPLE TOPS	
Shale & Lime	252		
Clay	400		
Anhydrite	696	Lansing K.C.	2454 -1026
Lime & Shale	1410	Mississippi	3154 -1726
Shale & Lime	1980	Kinderhook	3521 -2093
Lime	2229	Misener	3545 -2117
Lime & Shale	2280	Hunton	3551 -2123
Shale & Lime	2420	Maquoketa	3585 -2157
Lime & Shale	2580	Viola	3664 -2236
Lime	2778	Simpson Dolomite	3696 -2268
Lime & Shale	2894	Simpson Sand	3702 -2274
Lime	2010	Arbuckle	3781 -2353
Shale & Lime	3110	Rotary T.D.	3795 -2367
Lime & Shale	3174		
Lime	3336		
Lime & Chert	3440		
Lime	3535		
Shale	3555		
Lime & Shale	3650		
Shale & Lime	3689		
Lime	3703		
Sand	3730		
Shale	3782		
Lime	3795		
Rotary Total Depth	3795		

RECEIVED  
STATE CONSERVATION COMMISSION  
DEC 27 1968  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

*Arlo B. Romer*  
Arlo B. Romer

STATE OF KANSAS }  
COUNTY OF SEDGWICK } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 26th day of December, 1968.

*Martha Hartpence*  
Martha Hartpence-Notary Public

My Commission Expires:

April 21, 1971