


Perm CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Harvey County, Sec. 36 Twp. 22 Rge. 3 W (E) (W)
Location as "NE/CNWSW" or footage from lines NE NE NW
Lease Owner Harald Milburn
Lease Name Well Well No. I
Office Address 3803 Pomeroy Dr. Hutchinson, Kansas 67501
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed Sept 6 1973
Application for plugging filed March 19 74
Application for plugging approved March 19 74
Plugging commenced April 8 1974
Plugging completed April 9 1974
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? _____

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3299' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"		2905'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom of hole with sand. Sand from 3299' to 3100'. Dumped 4 ex of cement. Mudded hole to 220'. Made 10' of rack bridge. Dumped 25 ex of cement. Mudded hole to 40'. Made 10' of rack bridge. Dumped 10 ex of cement, filling to the bottom of the cellar.

RECEIVED
STATE CORPORATION COMMISSION
APR 11 1974
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Art Lamb Casing Pulling Co.
Address 2809 King St. Hutchinson, Kansas 67501

STATE OF Kansas COUNTY OF Reno, ss.
Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb
2809 King St. Hutchinson, Kansas 67501
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of April, 19 74.
Geedy Lamb
Notary Public.

My commission expires December 31, 1977



Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone (316) 241-1250

McPHERSON, KANSAS 67460

September 7, 1973

COMPANY: HAROLD J. MILBURN
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: WALL #1
 LOCATION: NE NE NW, Sec. 36-22-3W,
 Harvey County, Kansas
 COMMENCED: September 1, 1973
 COMPLETED: September 6, 1973
 ELEVATION: 1425 K. B.

0	to	30	Clay & Sand
30	to	60	Sand
60	to	181	Shale
181	to	575	Shale & Lime
575	to	1335	Lime
1335	to	1960	Shale & Lime
1960	to	2230	Lime
2230	to	2545	Shale
2545	to	2895	Lime
2895	to	3152	Lime & Shale
3152	to	3299	Mississippi
		3299	T. D.

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 19 1974
 CONSERVATION DIVISION
 Wichita, Kansas

Cut 12 1/4 inch hole to 181 ft. and run 182 ft. of 8 5/8 inch surface pipe, cemented with 150 sacks of cement at 181 ft., plug down at 4:30 P. M., September 1, 1973.
 Cut 7 7/8 inch hole to 3299. Run 3202 ft. of 4 1/2 inch pipe, cemented 1 ft. off bottom at 3298' with 50 sacks of cement. Plug down at 12:00 P. M., September 6, 1973.

TOPS: KANSAS CITY - 2431' MISSISSIPPI - 3152'

Measurements taken from K. B.

CERTIFICATE

I, Charles D. Johnson, Secretary-Treasurer of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your WALL #1, located on the NE NE NW, Sec. 36-22-3W, Harvey County, Kansas as reflected by the files of Blackstone Drilling, Inc.

[Signature]
 Charles D. Johnson - Secretary-Treasurer

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 7th day of September, 1973.

[Signature]
 Johnnie L. Schmidt - Notary Public

