


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
P. O. BOX 17027  
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plot

Harvey County. Sec. 36 Twp. 22S Rge. 3W (2x) (W)  
Location as "NE/CNW&SW" or footage from lines. C NW SW  
Lease Owner. Daskocil Sausage Company, Inc.  
Lease Name. C. L. Wall #1 Well No. 1  
Office Address. 9 North Main, South Hutchinson, Kansas 67505  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed. February 23, 1976 19  
Application for plugging filed. February 23, 1976 19  
Application for plugging approved. February 23, 1976 19  
Plugging commenced. 2:30 PM, February 23, 1976 19  
Plugging completed. 3:30 PM, February 23, 1976 19  
Reason for abandonment of well or producing formation. Dry Hole

If a producing well is abandoned, date of last production. 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Hugh-Scott- Yes

Name of Conservation Agent who supervised plugging of this well. Hugh Scott  
Producing formation. Depth to top. Bottom. Total Depth of Well. 3250'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	246'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud.  
Heavy mud to 260', 35 sacks cement;  
heavy mud to 40', solid bridge, 15  
sacks cement. 2 sacks in rathole.

2-26-76

RECEIVED  
STATE CORPORATION COMMISSION

FEB 26 1976

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor. Sterling Drilling Company CONSERVATION DIVISION  
Address. P. O. Box 129, Sterling, Kansas 67579 Wichita, Kansas

STATE OF KANSAS COUNTY OF RICE  
Bernard Laudermilk, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) Bernard Laudermilk  
Bernard Laudermilk, President  
P. O. Box 129, Sterling, Kansas 67579 (Address)

Subscribed and sworn to before me this 24th day of February 1976

CHARLES HALL—NOTARY PUBLIC  
My Commission Expires Jan. 6, 1978

Charles M. Hall, Notary Public.



STERLING DRILLING COMPANY  
 P. O. Box 129  
 Sterling, Kansas 67579

WELL LOG ----- C. L. WALL #1  
 Located: C NW SW, Section 36-22S-3W, Harvey County, Kansas

OWNER: Daskocil Sausage Company, Inc.  
 ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: February 17, 1976  
 COMPLETED: February 23, 1976

TOTAL DEPTH: 3250'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 250 Sand, Shale	Ran 5 joints new 10 3/4" casing, 235.33' set at 246' K.B. with 240 sacks 60/40 Pozmix with 3% cc. Plug down at 5:00 PM, 2-17-76.
250 - 1720 Lime and Shale	
1720 - 1750 Sand and Lime	
1750 - 3090 Lime and Shale	
3090 - 3200 Lime	
3200 - 3250 Mississippi	Plugged.

RECEIVED  
 FEB 26 1976  
 OFFICE WALL DIVISION  
 Wichita, Kansas