

## Blackstone Drilling, Inc.

Box 455104 523 West Kansas Phone (316) 241-1250  
McPHERSON, KANSAS 67460

September 18, 1978

COMPANY: KENNETH R. STUCKY  
CONTRACTOR: BLACKSTONE DRILLING, INC.  
FARM: C. L. WALL #1  
LOCATION: 900' NSL & 900' EWL SW/4 Sec. 36-22-3W,  
Harvey County, Kansas  
COMMENCED: September 9, 1978  
COMPLETED: September 17, 1978  
ELEVATION:

0	to	110	Sand
110	to	180	Blue Shale
180	to	735	Shale & Lime
735	to	930	Lime & Shale
930	to	1285	Shale & Lime
1285	to	2283	Lime & Shale
2283	to	2505	Shale & Lime
2505	to	2690	Lime & Shale
2690	to	2855	Lime
2855	to	3132	Lime & Shale
3132	to	3176	Shale & Lime
3176	to	3255	Mississippi
		3255	T. D.

RECEIVED  
STATE GEOLOGICAL COMMISSION

SEP 27 1978

CONSERVATION DIVISION  
WICHITA, KANSAS


Cut 12 $\frac{1}{2}$ " hole to 172' and run 174' of 8 5/8" surface pipe, cemented with 175 sacks of cement at 172'. Plug down at 1:15 P. M., September 9, 1978. Cut 7 7/8" hole to 3255'. Hole dry and abandoned. Set plug at 200' with 25 sacks of cement. Filled with mud to 40', cemented with 10 sacks of cement, 2 sacks in rat-hole. Plugging completed at 12:30 P. M., September 18, 1978 by State Plugger, Don Thompson, El Dorado, Kansas.

TOPS: MISSISSIPPI - 3176'

Measurements taken from K. B.

### CERTIFICATE

I, P. E. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your C. L. Wall #1, located on the 900' NSL & 900' EWL SW/4 Section 36-22-3W, Harvey County, Kansas as reflected by the files of Blackstone Drilling, Inc.

  
P. E. Plouffe, President  
by Charles D. Johnson, Sec'y-Treasurer

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 18th day of September, 1978.

  
Johnnie L. Schmidt - Notary Public

