

LEASE NAME Dan Ewy

WELL NUMBER 12

 Ft. from S Section Line

C NE SW Ft. from E Section Line

SEC. 17 TWP. 22S RGE. 22W (E) or (W)

COUNTY Hodgeman

Date Well Completed 8-12-62

Plugging Commenced 9-10-93

Plugging Completed 9-13-93

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Berexco, Inc.

ADDRESS Box 723 Hays, Kansas 67601

PHONE# (913) 628 6101 OPERATORS LICENSE NO. 5363

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-13-93 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4556

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	254	8 5/8		
	Casing	0	4551	5 1/2		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each section.
 Perf. 2 shots at 975'. Run tbg. openended to 4455'. Spot 25 sk. 60/40 pos. 6% gel. 200# hulls. Pull 113 jts to 985'. Mix 120 sk 60/40 pos 6% gel Circulate to surface. Hook to 5 1/2 casing MIX 80 sk. 60/40 pos. 6% gel Max. pressure 350# Shut in 0#. Hook to surface MIX 100 SK. 60/40 pos MIX, 6% gel. Max. pressure 300#. Shut in 0#.

Name of Plugging Contractor Berexco, Inc. License No. 5363

Address Box 723 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford

(Employee of Operator) STATE CORPORATION COMMISSION

above-described well, being first duly sworn on oath, says: That I have knowledge of the above-described well and the log of the above-described well and the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 723 Hays, Kansas

9-27-93
 RECEIVED
 SEP 27 1993
 CONSERVATION DIVISION
 KANSAS

NOTARY PUBLIC-State of Kansas
 ROSEMARY SMITH
 My Appt. Exp. 5-1-1995

SUBSCRIBED AND SWORN TO before me this 24 day of September, 19 93

Rosemary Smith
 Notary Public

My Commission Expires: 5-1-1995

USE ONLY ONE SIDE OF EACH FORM