


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Hodgman County, Sec. 17 Twp. 22 Rge. 22 (E) W (W)
Location as "NE/CNW%SW%" or footage from lines SW NE
Lease Owner Rains & Williamson Oil Company
Lease Name Emy "B" Well No. 3
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-7-63 19 63
Application for plugging filed 10-3 19 63
Application for plugging approved 10-3 19 63
Plugging commenced 10-3-63 19
Plugging completed 10-7-63 19
Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4532 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	257'	None
				4-1/2"	4530'	3704'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, sanded hole from 4532' to 4520' and dumped 5 sacks of cement with dumpbailer. Pulled 4 1/2" casing to 700' and pumped in 25 sacks of cement @ 700'. Mudded to 250' and pumped in 25 sacks of cement. Mudded hole to 50', set rock bridge to 40' and ran 15 sacks of cement to base of cellar. Welded on 8-5/8" cap.

RECEIVED
STATE CORPORATION COMMISSION

OCT 14 1963

10-14-63

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS
(If additional description is necessary, use BACK of this sheet)

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of October, 1963

My commission expires May 20, 1964

Milton J. Volin
Notary Public.



ROTARY DRILLING LOG

15-083-10225-0000

OPERATOR: Rains & Williamson Oil Co.
#3 EWY "B", SW NE
Section 17-22S-22W
Hodgeman County, Kansas

CONTRACTOR: Rains & Williamson
Oil Co.
COMMENCED: 8-27-63
COMPLETED: 9-7-63

Remarks: Set 8-5/8" casing
at 257.18' with
135 sacks cement

Set 4-1/2" casing
2' off bottom w/100
sacks cmt.

Formations

Surface Clay	40'
Shale	165'
Sand	175'
Shale	825'
Anhydrite	840'
Shale and Red Bed	925'
Sand	1130'
Shale	1260'
Shale and Red Bed	1440'
Anhydrite	1475'
Shale and Shells	2150'
Shale and Lime	2430'
Lime and Shale	2925'
Shale and Lime	3665'
Shaley Lime	3860'
Lime and Shale	4337'
Lime	4532'
 Rotary Total Depth	 4532'

RECEIVED
STATE CORPORATION COMMISSION

OCT 14 1963

CONSERVATION DIVISION
Wichita, Kansas


We certify the above log is
true and correct to the best of
our knowledge and belief.

RAINS & WILLIAMSON OIL CO.



Wilson Rains
Partner

Subscribed and sworn to before me, a
Notary Public in and for the State of
Kansas, County of Sedgwick, this 16th
day of September, 1963.



Sherry Gish Notary Public

My Commission Expires:
November 8, 1966