

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15.083-10223-0000

LEASE NAME Ewy A-4

WELL NUMBER _____

SPOT LOCATION C NE SE

SEC. 17 TWP. 22S RGE. 22W (E) or (W)

COUNTY Hodgeman

Date Well Completed _____

Plugging Commenced 2-23-84

Plugging Completed 2-29-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Braden-Deem, Inc.

ADDRESS Suite 1250 125 N. Market Wichita, Ks. 67202

PHONE # (913) 483-2532 OPERATORS LICENSE NO. _____

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4490'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	284'	none
				5-1/2"	4485'	1511'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4410' and 5 sacks cement. Shot casing @2000', 1811', 1619', 1511' and pulled a total of 58 joints (1511') of 5-1/2" casing. Plugged surface with 3 hulls, 10 gel, 70 cement, 10 gel, 1 hull, released plug and displaced with 130 cement, 60/40 pos, 2% gel, 3% cc. Plugging Complete.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

MAR 07 1984

SUBSCRIBED AND SWORN TO before me this 5th day of March, 1984

CONSERVATION DIVISION
Wichita, Kansas
My Commission expires:



Irene Hoover
Notary Public