

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.--82-3-117

API NUMBER. 15-185-20696-0000

LEASE NAME Dale

WELL NUMBER #1

 Ft. from S Section Line

 Ft. from E Section Line
 NW SE NE

SEC. TWP. RGE. (E) or (W)

COUNTY Stafford

Date Well Completed 12-29-76

Plugging Commenced 2-29-88

Plugging Completed 3-3-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Patton Oil Company

ADDRESS 672 W. 4th Street
 Hoisington, Kansas 67544

PHONE#(316) 653-2277 OPERATORS LICENSE NO. 5992

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3900'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	239'	none
				5-1/2"	3895'	2847'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 3550' and 5 sacks cement. Shot pipe @3112', 2847', pulled a total of 69 joints of 5-1/2" casing. Plugged surface with 4 hulls, 10 gel, 50 cement, 10 gel, 1 hull, plug and 100 cement, 60/40 pos, 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 8th day of March, 1988

James Hoover
 Notary Public
 STATE CORPORATION COMMISSION

My Commission Expires:



LEAR - 3-9-88 For CP-4 Revised 07-86

DRILLERS LOG

15-185-20696-0000

No. 1 Dale

CASING RECORD:

COMPANY: Patton Oil Company

DESCRIPTION:

3 5/8" @ 239'
w/225 sx cmt.

CONTRACTOR: Red Tiger Drilling Company

NW SE NE
Sec. 18-T23S-R12W
Stafford County, Kansas

5 1/2" @ 3895'
w/150 sx cmt.

COMMENCED: December 17, 1976

COMPLETED: December 29, 1976

TOTAL DEPTH: 3,900'

ELEVATION: 1,865 GL

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface hole	0	239	
Shale	239	620	
Shale & Red Bed	620	717	
Anhydrite	717	736	
Shale	736	1645	
Shale & Lime	1645	2070	
Lime & Shale	2070	2240	
Shale	2240	2430	
Shale w/Lime Streaks	2430	2635	
Lime & Shale	2635	3335	
Lime	3335	3785	
Lime, Chert, Shale	3785	3871	
Arbuckle	3871	3900	
RTD		3900	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 3rd day of January, 1977.

James A. Hagerman
Notary Public

RECORDED
JAN 12 1977
STAFFORD COUNTY, KANSAS