

15-185-00123-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Stafford County, Sec. 19 Twp. 23 Rge. 12 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NW SW

Lease Owner Petroleum, Inc.

Lease Name MEYER Well No. 1

Office Address 305 East 3rd, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed December 5, 19 53

Application for plugging filed December 5, 19 53

Application for plugging approved December 5, 19 53

Plugging commenced December 5, 19 53

Plugging completed December 5, 19 53

Reason for abandonment of well or producing formation

Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 3916 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	233'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 230' and set wooden plug at 230'. Placed 1/3 sack hulls on top of plug at 230'. Cemented and displaced 20 sacks cement through drill pipe onto plug and hulls at 230'. Mudded up to 40' and set second wooden plug at 40'. Placed 1/3 sack hulls on top of plug at 40'. Filled hole to bottom of well cellar with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company

Address R.R. #2, Great Bend, Kansas.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. W. W. Fisher (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. W. Fisher

305 East 3rd Street, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 20th day of December, 19 53

Charles J. [Signature] Notary Public.

My commission expires October 13, 1954.

PLUGGING
FILED SEC 19 T 23 R 12W
BOOK PAGE 442 LINE 39

1-6-54

DRILLER'S LOG MEYER #1

15-185-00123-0000

Petroleum, Inc., Operator

Section 19, Twp. 23S, Rge. 12W.

Contractor, Garvey Drilling Company

Location: NE NW SW

Drilling Commenced: November 22, 1953.

County: Stafford County, Kansas.

Drilling Completed: December 5, 1953.

Production: D & A

Casing Record: 8 5/8 @ 233' w/225 sax.

Figures below indicate bottom of formation:

- 110 Sand, Clay & Gravel
- 233 Shale & Shells with Sand Streaks
- 300 Red Bed & Shale
- 718 Red Bed, Sand Streaks & Shale
- 740 Anhydrite
- 1230 Shale & Shells
- 1400 Salt & Shale
- 3492 Lime & Shale
- 3752 Lime
- 3762 Conglomerate & Shale
- 3809 Conglomerate & Lime
- 3824 Chert
- 3869 Shale & Sand
- 3911 Lime & Shale
- 3915 Lime
- 3916 R.T.D.

Tops:

- Heebner: 3277 (-1397)
- Brown Lime: 3415 (-1535)
- Lansing: 3440 (-1560)
- Viola: 3758 (-1878)
- Simpson: 3814 (-1934)
- Arbuckle: 3910 (-2030)

I hereby certify that this is a true and correct log of the above mentioned well.

PETROLEUM, INC.

By

W. W. Finch

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 13th day of December, 1953.

Charles H. Hester
Notary Public

My commission expires: October 13, 1954.

PLUGGING
FILE SEC 19 T 23 R 12W
BOOK PAGE 147 LINE 39