

15-185-01617-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

FORMATION PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Strike out upper line
when reporting plugging
off formations.

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 21 Twp. 23S Rge. (E) 12 (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. NW SE SW
Lease Owner Shell Oil Co., Inc.
Lease Name Ada Bean Well No. 2
Office Address Box 744, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed November 11 1940
Application for plugging filed May 8 1946
Application for plugging approved May 13 1946
Plugging commenced June 8 1946
Plugging completed June 12 1946
Reason for abandonment of well or producing formation Oil Depleted
If a producing well is abandoned, date of last production October 8 1945
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well H. W. Kerr
Producing formation Arbuckle Depth to top 3848 Bottom Total Depth of Well 3875 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Ind. Cap. 8255 bbls fluid 91.3% water	3848	3857	8 5/8" 1 1/2"	270' 3875'	None 1550'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Ran 4 sack cement on bottom. Mudded hole to 260'.
Set 10' rock bridge & capped with 15 sack cement
at 250'. Filled surface casing with mud & capped
with 10 sack cement.

FILE 21 23 8120
BOOK PAGE 54 OF 9

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Shell Oil Co., Inc.
Address c/o W. M. Gholson, Box 744, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, SS.
W. M. Gholson (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 744, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of July, 1946.

Betty Postlethwaite
Notary Public.

My commission expires January 24, 1949

15-185-01617-0000

SHELL, ADA BEAN #2
NW SE SW Section 21-23S-12W
Stafford County, Kansas
Bedford Pool

CASING RECORD

8 5/8" Cem 270 with 125 sax
4 1/2" Cem 3875 with 100 sax; perforated
3848-57.

0 - 35 Soil & sand
 275 Sand & red rock
 505 Red rock
 710 Red bed
 743 Anhydrite
 1162 Shale & shells
 1340 Salt & shale
 1455 Shale & shells
 1480 Lime
 1529 Lime & shale streaks
 1625 Broken lime
 1650 Shale & lime streaks
 1698 Lime & shale streaks
 1730 Lime
 1784 Shale, lime & chert
 1834 Lime
 1856 Shale
 1867 Lime
 1930 Shale & lime
 2000 Shale & lime
 2040 Broken lime
 2064 Lime
 2075 Shale
 2115 Lime
 2125 Shale
 2217 Shale & lime streaks
 2238 Lime
 2315 Shale & lime streaks
 2400 Shale & shells
 2594 Shale & lime streaks
 2625 Lime
 2663 Shale
 2818 Shale & lime streaks
 2865 Shale & lime
 2912 Shale & lime streak
 2931 Lime
 2945 Broken lime
 3038 Lime
 3095 Lime & shale
 3154 Lime
 3170 Shale & lime
 3188 Lime
 3233 Lime, shale & streaks chert
 3284 Lime
 3360 Lime & shale

3397 Shale & lime streaks
 3455 Lime
 Top Lans.Kans.City 3400
 3470 Shale & lime
 3528 Lime
 3535 Lime, sandy
 3572 Lime & shale streaks
 3692 Lime
 3709 Conglomerate
 Top Sooy Conglomerate 3692
 3725 Chert & shale
 Top Viola 3709
 3743 Chert & some shale
 3770 Chert
 3781 Chert & shale
 3808 Shale
 Top Simpson 3781
 3810 Sandy lime & dolomite
 3815 Sand
 3822 Shale
 3846 Shale with sand streaks.
 3848 Brecciated dolomite, sand grains & chert
 Top Brecciated Arbuckle 3846
 3875 Dolomite TD
 Top Arbuckle 3848
 3857 FB

PLUGGING
 FILE 21-23-12W
 COOK PAGE 54 OF 9

STATE OF KANSAS
 MAY 11 1946
 CITY