

15-185-01518-0600

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging of formations.

NORTH



Locate well correctly on above  
Section Plat

Stafford County. Sec. 21 Twp. 23S Rge. (E) 12 (W)  
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. SE SE SW  
Lease Owner. Shell Oil Co., Inc.  
Lease Name. Ada Bean Well No. 1  
Office Address. Box 744, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole). Oil  
Date well completed. September 2 19 40  
Application for plugging filed. May 8 19 46  
Application for plugging approved. May 13 19 46  
Plugging commenced. June 6 19 46  
Plugging completed. June 8 19 46  
Reason for abandonment of well or producing formation. Oil Depleted

If a producing well is abandoned, date of last production. July 12 19 44  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well. H. W. Kerr  
Producing formation. Arbuckle-Lans-KansCity Depth to top. 3839 Bottom. Total Depth of Well. 3854 Feet  
Show depth and thickness of all water, oil and gas formations. 3396(IK) 3505(PB)

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	Ind. Cap. 18, 100 bbls 10% water	3840	3854	8 5/8" 1 1/2"	263' 3840'	None 1581'
Lansing-Kansas City	2,170M cu ft gas	3419 3435 3446 3458 3467 3482 3498	3424 3435 3447 3459 3472 3490 3503			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Dumped 2 sax cement on bottom. Mudded hole to 260'.  
Set 10' rock bridge & capped with 15 sax cement. Filled  
surface pipe with mud & capped into base of cellar with  
10 sax cement.

FILED 21 23 1946  
BOOK 54 PAGE 8

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. Shell Oil Co., Inc.  
Address. c/o W. M. Gholson, Box 744, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, SS.  
W. M. Gholson (employee of owner)

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) *W. M. Gholson*

Box 744, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of July, 1946.

*Betty Pestlethwaite*  
Notary Public.

My commission expires January 24, 1949

7-18-46

15-185-01515-0000

SHELL, ADA BEAN #1  
SE SE SW Section 21-23S-12W  
Bedford Pool  
Stafford County, Kansas

CASING RECORD

8 5/8" Cem 263 with 125 sax  
4 1/2" Cem 3840 with 100 sax \*\*

0 - 110	Surface soil & sand	3686	Lime & shale
250	Shale & shells	3715	Lime & chert
650	Red rock	3717	Chert
675	Red rock	3717=3715	SLC
695	S lt & chalk		Top Sooy Conglomerate 3706
740	Sand		Top Viola 3712
820	Red rock	3720	Chert & shale
1421	Shale & shells	3737	Chert & shale
1464	S, lt, shale & shells	3740	Chert
1474	Lime	3755	Chert & streaks dolomite
1617	Shale & shells	3759	Dolomite & chert.
1756	Lime & shale	3761	Chert
1765	Lime, chert & shale	3767	Chert & dolomite
1798	Lime & chert	3769	Shale
1862	Lime & shale	3772	Lime & streaks shale
1945	Lime, shale & chert streaks	3773	Sand & shale
1979	Lime		Top Simpson Shale 3772.
2015	Lime & shale	3798	Shale with dolomite
2024	Lime		Top Simpson Sand 3798
2058	Lime & shale	3805	Sand & shale streaks
2118	Lime	3808	Sand
2214	Lime & shale	3809	Shale with sand grains
2407	Lime	3839	Shale with sand graind & dolomite
2465	Lime & shale		Top Arbuckle 3839 SLC
2498	Lime	3854	Dolomite TD
2750	Lime & shale	3505	PB
2760	Lime & chert		
2908	Lime & shale		**Perforated 3498-3503; 3482-90;
2938	Lime		3467-72; 3458-59; 3446-47; 3435-36;
2950	Lime, shale & chert		and 3419-24
	Top Topeka 2946		
2982	Lime, sand & chert		
3040	Lime & streaks chert		
3083	Lime		
3090	Lime & chert		
3100	Lime		
3112	Lime & chert streaks		
3130	Lime & chert		
3170	Lime		
3292	Lime & chert		
3323	Lime & shale		
3323=3326	SLC		
3372	Lime & some chert		
	Top Lans.Kans.City 3396		
3427	Lime, shale & chert		
3459	Lime		
3523	Lime & chert		
3599	Lime		
3646	Lime & some chert		
3660	Lime		

21 23 12.10  
54 8

MAY 11 1946