

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

15-185-01094-6000
WELL PLUGGING RECORD

Stafford County, Sec. 21 Twp. 23 Rge. 12W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NW NE

Lease Owner Mull Drilling Co. Inc.

Lease Name McGill Well No. 1

Office Address 670 N. 4th. Natl. Bank Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 6-15 19 60

Application for plugging filed 6-15 19 60

Application for plugging approved 6-15 19 60

Plugging commenced 10:00 P. M. 6-15 26 19 60


Plugging completed 12:00 P. M. 6-15 26 19 60

Reason for abandonment of well or producing formation

No Production

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot.

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3880' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				STATE CORP.		7-13-60
				JUL 13 1960		ON
				CONSERVATION DIVISION WICHITA, KANSAS		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole was filled to within 240' of top of surface with drilling mud, No. 1 plug was pushed to this depth with drill pipe 1/2 sack hulls put on top of plug and 20 sacks cement put on top of hulls through drill pipe. No. 2 plug put in hole to depth of 30' after hole was filled to this depth with drilling mud. 1/2 sack hulls put on top of plug and 10 sacks cement added through drill pipe. This completed plugging of hole. 2 sacks cement put in rat hole to plug same.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Co. Tools

Address

STATE OF Kansas COUNTY OF Sedgwick, ss.

Joseph O. Butts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joseph O. Butts

(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of June, 19 60

Madge N. Miller
Notary Public.

My commission expires Feb 24 1964

15-185-01094-0000

ROTARY DRILLERS LOG

COMPANY: Mull Drilling Co., Inc. Et Al. ROTARY DRILLING COMMENCED: 6/13/60
 Wichita, Kansas


CONTRACTOR: Mull Drilling Co., Inc. ROTARY DRILLING COMPLETED: 6/22/60
 Wichita, Kansas

CASING RECORD: 260' of 8 5/8" csg. LOCATION: McGill #1
 w/200 sax cmt. C NW NE 21-23-12
 D & A - no log run Stafford County, Ks.

(Figures indicate bottom of formation - measurements from top of Rotary Bushing.)

1277'	Red Bed, etc.
1630'	Shale & Shells
1790'	Lime w/Shale
2105'	Lime
3048'	Lime & Shale
3170'	Sandy Lime & Shale
3294'	Sandlime & Shale
3540'	Sandy Lime & Shale
3742'	Lime w/Shale
3804'	Viola Lime & Chert
3869'	Simpson
3880'	Arbuckle - D.&A

I hereby certify that is a true and correct copy of the above log to the best of my knowledge.

MULL DRILLING COMPANY, INC.

 R. James Gear

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 11 1962
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 30th day of June, 1960




 Notary Public