


15-185-12135-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County, Sec. 26 Twp. 23 Rge. 12 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW NW SE
Lease Owner Trans Era Petroleum, Inc.
Lease Name Lambe Well No. 1
Office Address Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4/13/54 19
Application for plugging filed 4/12/54 19
Application for plugging approved 4/12/54 19
Plugging commenced 4/13/54 19
Plugging completed 4/13/54 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3938 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	246	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING RECORD

Finished laying down drill pipe. Filled hole with heavy mud to 240', set first plug at 240' with one-fourth sack of hulls and 20 sacks of cement mixed and run through drill pipe. Filled hole with mud to 40', set second plug at 40', one-fourth sack of hulls and 10 sacks of cement were used.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor TRANS ERA PETROLEUM, INC.
Address Russell, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
H. R. Michaelis (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) H. R. Michaelis
Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of April, 1954

My commission expires 1-30-57.

Margie Cooper
Notary Public.

24-7868-S 3-53-20M

PLUGGING
SEC 26 T 23 R 12W
COR 22 LINE 7

RECEIVED
STATE CORPORATION COMMISSION

APR 21 1954

4-23-54

CONSERVATION DIVISION
Wichita, Kansas

15-185-12135-0000

Frans Era Petroleum, Inc.
Lambe #1

NW NW SE 26-23-12
Stafford County, Ks.

Total Depth: 3938'
Comm. 3/30/54
Comp. 4/13/54

Casing

8 5/8" Set @ 246'

Cement

175 sacks of Lehigh

Formation	Depth
Sand	125
Red bed	160
Shale	246
Red bed-shale	623
Anhydrite	663
Shale-shells	1625
Lime-shale	3384
Lime	3738
Lime-shale	3812
Lime-chert	3830
Shale-sand	3836
Shale-chert	3885
Arbuckle	3938'

STATE OF KANSAS)
) ss
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

Cora Betz

Subscribed and sworn to before me this 21st day of April, 1954.

Margie Cooper

Notary Public

My commission expires: 1-30-57.

PLUGGING
FILE 26-23-12W
BOOK PAGE 22 LINE 7

NOTARY PUBLIC
STATE OF KANSAS