


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Finney County, Sec. 33 Twp. 21S Rge. (E) 33 (W)
Location as "NE/CNW/SW" or footage from lines C NE/4



Locate well correctly on above Section Plat

Lease Owner Kansas-Nebraska Natural Gas Company, Inc.
Lease Name Wilson B Well No. 1
Office Address P. O. Box 608, Hastings, Nebraska
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2/6 19 64
Application for plugging filed 2/17 19 64
Application for plugging approved 2/19 19 64
Plugging commenced 3/2 19 64
Plugging completed 3-5 19 64
Reason for abandonment of well or producing formation Non productive formation
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh E. Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2652 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Hollenberg	water	2578	2585	8 5/8	304	none
Herrington	water	2611	2622	5 1/2	2652	1437
Krider	water	2625	2638			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back to 2596 with 40 gallon rock. Dumped 20 sacks cement with dump bailer, Top cement at 2430'. Pulled 1437' of 5 1/2" casing.
Bridged hole at 700' and dumped 25 sacks cement with dump bailer. Plug 700' - 565'
Bridged hole at 300' and dumped 25 sacks with dump bailer. Plug 300' - 150'
Bridged hole at 45' and dumped 15 sacks cement with dump bailer for top plug.
Plug 45' to 8'

RECEIVED
STATE CORPORATION COMMISSION
04-13-64

APR 13 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor C. L. Hinds
Address Liberal, Kansas

STATE OF Nebraska, COUNTY OF Adams, ss.
S. D. Ford, Jr. (employee of owner) ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. D. Ford, Jr.
P. O. Box 608, Hastings, Nebraska
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of April, 1964

My commission expires January 23, 1970

F. S. White
Notary Public.