

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-24

SPOT LOCATION C SW

SEC. 24 TWP. 21 RGE. 33 (E or W)

LEASE OPERATOR Unico Inc.

COUNTY Finney

ADDRESS 165 S. Union Blvd., Suite 602
Lakewood, CO 80228

02-15-91

FEB 15 1991

Date Well Completed 9-20-1961

PHONE # (303) 980-1277

OPERATORS LICENSE NO.

Plugging Commenced 1-20-1991

Character of Well Gas
(Oil, Gas, D&A, SHD, Input, Water Supply Well)

Plugging Completed 1-28-1991

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? yes if not, is well log attached?

Producing formation Hugoton Depth to top 2609 bottom 2658 T.D. 2671'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface				7"	341'	0'
Production				4 1/2"	2671'	840'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Pump 2 sks. hulls & 20 sks. cement to 2400' - Pressured to 700 lbs. - Pump 60 sks. cement 815' to 575' Mud 575' to 370' - Pump 40 sks. cement 370' to 210' Mud 210' to 40' - Bride + 10 sks. cement 40' to 3' Cut off 7", 3' below ground level and cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Midwest Casing Pulling Service License No. 6497


Address Box F, Sublette, Ks. 67877

STATE OF KANSAS COUNTY OF HASKELL, ss.

I, Edgar J. Eves (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Edgar J. Eves

(Address) Box F, Sublette, Ks. 67877



SUBSCRIBED AND SWORN TO before me this 3rd day of Feb., 1991

Sondra L. Eves
Notary Public

My Commission expires: 12-6-92