


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Finney County, Sec. 17 Twp. 21S Rge. (E) 33 (W)

Location as "NE/CNW&SW" or footage from lines. C SE SE
Lease Owner Eureka Drilling Company
Lease Name Wampler Well No A-1
Office Address Hamilton, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Abandoned
Date well completed 19____
Application for plugging filed December 22 19.67
Application for plugging approved December 23 19.67
Plugging commenced December 23 19.67
Plugging completed December 31 19.67
Reason for abandonment of well or producing formation no oil

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production December 21 19.67
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well E. Eves
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4695 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

8 5/8 to 240' circulated w/cement
5 1/2 to 4,692' cemented
Top perfs. 4,189'
Plug bottom w/30 sacks.
Top of cement 3,800'
Mud 3,800 to 600'
Spot 40 sacks 600' to 470'
Mud 470' to 240'
Spot 25 sacks 240' to 140'
Mud 140' to 40'
Plug hulls and 10 sacks 40' to 0'
Pulled 2,002' 5 1/2
Completed 12/31/67

RECEIVED
STATE CORPORATION COMMISSION
JAN 29 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Eureka Drilling Company
Address Hamilton, Kansas

STATE OF Kansas, COUNTY OF Greenwood, ss.
R. K. Teichgraeber (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. K. Teichgraeber
Hamilton, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 26th day of January, 19 68

WALKER ELLIS NOTARY PUBLIC
Greenwood County, Kansas
My commission expires Aug. 9, 1970

Walker Ellis
Notary Public.

Wampler, Lease. Well No. A-1
 Loc C SE SE Sec. 17 Twp. 21S Rge. 33W
 County Finney State Kansas
 Pool Wildcat

Spud Date 8-24-59
 Rotary Completed 9-2-59
 Completion Date 9-6-59
 Potential 855 BOPD
 Gravity 31.4 @ 78
 R. T. D. 4695

Surface casing set at (8 5/8) 215 with 225 sacks
 Production casing set at (5 1/2) 4692 with 175 sacks

Formation Top: 2893 RB
 Elevation:

Sample

Electric Log

Hollenberg	2478	(+ 415)	
Herrington	2438	(+ 155)	2489 (+ 404)
Krider	2516	(+ 377)	
Windfield	2570	(+ 323)	
Doyle	2596	(+ 297)	
Topoka	3566	(- 673)	
Hoebner	3772	(- 879)	
Toronto	3793	(- 900)	
Lansing	3815	(- 922)	
Base Kansas City	4260	(-1367)	
Marmaton	4276	(-1383)	
Cherokee	4432	(-1539)	
Morrow	4572	(-1679)	
Mississippi	4620	(-1727)	

PRODUCING AND PROSPECTIVE PRODUCING ZONES 4695

Formation	Depth	Feet	Remarks	Estimated Reserves
Kansas City	4182-88	4	DST 585' 0, 120' HOCM, BHP 1066#	15,350
Marmaton	4276-91	15	Perf. 4278-90	64,300

This is only log we have

Completion Date: 9-4-59
 Moved in Franks #2. SHD.
9-5-59

Set Halliburton limit plug at 4340. Dumped 2 sacks cement on top of plug. Perf. Marmaton from 4278-90, 4 Jets per ft. Swabbed 10 BOPD natural for 7 hrs. Acidized with 3000 gal. Gel. MP 1250#. Final pressure 750#. 3 min. PD 450#. Shut well in 4 hrs. SBL.

RECEIVED
 STATE CONSERVATION COMMISSION

DEC 29 1967

CONSERVATION DIVISION
 Wichita, Kansas