

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-055-00053-0000
API NUMBER Completed on 4-12-60

LEASE NAME Hyer A

WELL NUMBER 1

660 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 16 TWP. 21S RGE. 33 (W)

COUNTY Finney

Date Well Completed 4-12-60

Plugging Commenced 11-20-85

Plugging Completed 12-9-85

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Cities Service Oil and Gas Corporation

ADDRESS 3545 NW 58th Street, Oklahoma City, OK 73112

PHONE#(405) 949-4432 OPERATORS LICENSE NO. 5447

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well).

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District Office #1

Is ACO-1 filed? completed on 4-12-60 if not, is well log attached? not available

Producing Formation Lansing-Kansas City Depth to Top 4185' Bottom 4188' T.D. 4715'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
L-KC	oil	4185	4188	8-5/8"	225'	0'
				5-1/2"	4714'	1019'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

11-20-85: Set CIBP at 4000' KB & dumped 2 sx cmt on top of plug. 12-9-85: Loaded hole w/34 bbls of mud. Shot csg at 1029'. Set cmt plugs as follows: 80 sx at 1029', 50 sx 252', 10 sx at 40' to surf. Cut off csg 6' below GL. Welded on plate. Well P & A on 12-9-85

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor DACO License No. _____

Address Drawer 3010, Borger, Texas 79007

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Del G. Oliver, Engineering Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Del G. Oliver

(Address) 3545 NW 58th Street Oklahoma City, Oklahoma 73112

SUBSCRIBED AND SWORN TO before me this 5 day of February, 1986

Terese Jo Holveth
Notary Public

My Commission Expires: 4-24-89

RECEIVED
STATE CORPORATION COMMISSION
02-06-86
FEB 6 1986
Form CP-4
Revised 08-84