

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-055-00181-0000
 API NUMBER N/A

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE NAME HOBBS

WELL NUMBER #1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 15 - TWP. 21 RGE. 33W (E) or (W)

COUNTY FINNEY

Date Well Completed

Plugging Commenced 1/8/88

Plugging Completed 1/13/88

LEASE OPERATOR A. L. ABERCROMBIE, INC.

ADDRESS 801 Union Ctr. Bldg., Wichita, KS 67202

PHONE#(316 262-1841 OPERATORS LICENSE NO. 5393

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist#1 Dodge City, KS

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 2657½'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				7"	350'	None
				4½"	2657'	1259.80'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
 Pumped bottom to 1342' with 1 Hull & 20 sacks cement using Allied. Shot pipe @ 1259' and pulled a total of 37 joints of 4½" casing. Plugged surface with 4 hulls, 10 gel, 60 sacks cement, 10 gel, 1 Hull, 150 sacks cement, 60/40 poz, 6%gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347, Chase, KS 67524

STATE OF KANSAS COUNTY OF RICE, ss. 01-20-88

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 20 1988

MIKE KELSO, VICE-PRESIDENT (Employee of Operator) or (Operator) or (Owner) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well and certify that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) Box 347, Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 18 day of JANUARY, 19 88

Jane Hoover
 Notary Public

My Commission Expires:



DRILLER'S LOG

Musgrove Drilling Company
801 Union Center
Wichita, Kansas

Hobbs # 1
C SE, Sec. 15-21S-33W
Finney County, Kansas

Total Depth: 2657'

Commenced: 4/10/61 Completed: 4/14/61

Elevation: 2903' KB

Contractor: Chemical & Technical Services, Inc.
P. O. Box 728
Hill City, Kansas

Casing Record: Set 7" surface pipe at 350' with 125 sacks cement
Set 4-1/2" casing at 2657' with 75 sacks cement.

Figures indicate bottom of formations:

			<u>TOPS</u>
Sand & Shale	1105'		
Shale & Sand	1570'	Anhydrite	2084' (+819)
Shale	2084'	Rotary Total Depth	2657' (+246)
Anhydrite	2096'		
Shale	2555'		
Lime & Shale	2657'		
Total Depth	2657'		

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

CHEMICAL & TECHNICAL SERVICES, INC.

By: Daniel F. McLeath
Asst. Treasurer

Subscribed and Sworn to before me this 29th day of April, 1961.

Carroll G. Miller
Notary Public

STATE OF KANSAS

OCT 22 1961

CONSERVATION DEPARTMENT
Wichita, Kansas