

1030129

15-083.10095.0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- - Not available
, Sec. 26 , T 22 S, R 22 W/2

1980 feet from N/2 section line
1980 feet from W/2 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Hann "B" Well # 1

Operator: Cities Service Oil & Gas Corp.
Name & 800 Sutton Place,
Address Wichita, KS 67202

County Hodgeman

Well Total Depth 4402 feet 143.07

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 666

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Ness County Well Service License Number 7527

Address Box J, Ness City, KS 67560

Company to plug at: Hour: 8:30 am Day: 16 Month: June Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Bob Walters

(company name) Ness County Well Service (phone) 913-798-3615

were: 5 1/2 set at 4392

Spotted 6 sacks sand and 5 ssx cement at total depth. Dug out casing head on 8 5/8" casing. Pumped 30 sacks get down surface pipe and 5 1/2" casing.

Pulled 71 joints (2303') of 5 1/2" casing. Pumped down 8 5/8" casing - 3 sx hulls, 15 sx gel, 70 sx common cement, 15 sx gel, 1 sack hulls and 150 sx cement. Maximum pressure 1200# shut-in pressure 700#

Signed Steve Plummer (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:30 pm Day: 16 Month: June Year: 19 83

ACTUAL PLUGGING REPORT 5 1/2 set at 4392

Spotted 6 sx sand and 5 sx cement at TD. Dug out casing head on 8 5/8" casing. Pumped 30 sx get down surface pipe and 5 1/2" casing. Pulled 71 joints (2303') of 5 1/2" casing. Pumped down 8 5/8" casing - 3 sx hulls, 15 sx gel, 70 sx common cement, 15 sx gel, 1 sack hulls and 150 sx cement. Maximum pressure 1200# and shut-in pressure 700#

Remarks: Used common cement by Halliburton. They recovered 2300" of 5 1/2" casing. Paul Luthi witnessed the plugging

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

3-19-84

INVOICED
DATE 3-20-84
INV. NO. 0791

RECEIVED
STATE CORPORATION COMMISSION
MAR 1 6 1984
SIGNED Steve Plummer (TECHNICIAN)
CONSERVATION DIVISION
Wichita, Kansas