

1060157

TO: STATE CORPORATION COMMISSION 5-6 API NUMBER 15-083-21,187-0000  
NE SE NW/4 SEC. 26, T 22 S, R 22 W

CONSERVATION DIVISION - PLUGGING SECTION 1980 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2970 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME HANN WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY HODGEMAN 142.94

OPERATOR LICENSE # 31961 WELL TOTAL DEPTH 4398 FEET

OPERATOR: BURIED HILLS PRODUCTION PRODUCTION CSG: SIZE 5 1/2" @ 4394' WITH 125 SX

NAME AND 1050 17TH ST, STE 1550 SURFACE CASING: SIZE 8 5/8" @ 294' WITH 200 SX

ADDRESS DENVER, CO 80265

ABANDONED OIL WELL X GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D/A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR SWIFT SERVICES, INC LICENSE NUMBER 32382

ADDRESS PO BOX 466, NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 11:30 AM DAY: 06 MONTH: 05 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM DEAN IVES

(COMPANY NAME) SWIFT SERVICE, INC (PHONE) 785-798-2300

WERE: DV TOOL @ 1296' WITH 425 SX CEMENT.

MIX 35 SX CEMENT DISPLACE WITH 22 SX GEL AND FOLLOW WITH 125 SX CEMENT. HOOK ONTO BRADEN

HEAD AND MIX 35 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART \_\_\_\_\_ NONE \_\_\_\_\_

OPERATIONS COMPLETED: HOUR: 12:30 PM DAY: 06 MONTH: 05 YEAR: 1999

ACTUAL PLUGGING REPORT \_\_\_\_\_

PUMPED 200# HULLS WITH 40 SX CEMENT, 22 SX GEL THEN 110 SX CEMENT.

PRESSURED TO 1500#. SHUT IN WITH 1000#. WENT DOWN BACKSIDE AND PRESSURED RIGHT TO

500# AND HELD.

REMARKS: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (I.D.) **INVOICED** OBSERVE THIS PLUGGING. STATE CORP. COMMISSION  
MAY 26 1999 SIGNED Michael Maier/ymf (TECHNICIAN) FORM CP-2/3

DATE 6-3-99  
VOL. NO. 60998  
CONSERVATION DIVISION  
Wichita, Kansas

5-26-99

