

1060158

TO: STATE CORPORATION COMMISSION

5-6

API NUMBER 15-083-21,200-0000
NW NW NE SEC. 26 T 22 S, R 22 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2210 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME HANN WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY HODGEMAN 142.87

OPERATOR LICENSE # 31961

WELL TOTAL DEPTH 4396 FEET

OPERATOR: BURIED HILLS PRODUCTION PRODUCTION CSG: SIZE 5 1/2" @ 4394' WITH 125 SX

NAME AND 1050 17TH ST, STE 1550 SURFACE CASING: SIZE 8 5/8" @ 1294' WITH 475 SX

ADDRESS DENVER, CO 80265

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SWIFT SERVICES, INC LICENSE NUMBER 32382

ADDRESS PO BOX 466, NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 2:00 PM DAY: 06 MONTH: 05 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM DEAN IVES

(COMPANY NAME) SWIFT SERVICE, INC (PHONE) 785-798-2300

WERE: OPEN HOLE

MIX 35 SX CEMENT DISPLACE 15 SX GEL. PERFORATE AT 1300' WITH 310 SX CEMENT. CIRCULATE CEMENT BETWEEN 5 1/2" AND 8 5/8".

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 5:00 PM DAY: 06 MONTH: 05 YEAR: 1999

ACTUAL PLUGGING REPORT

ON BOTTOM PUMP 35 SX CEMENT WITH 200# HULLS.

1ST PLUG AT 1350' WITH 50 SX CEMENT.

2ND PLUG AT 650' WITH 40 SX CEMENT.

3RD PLUG AT 330' WITH 50 SX CEMENT.

4TH PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. RECOVERED 2300' OF 5 1/2" CASING.

INVOICED RECEIVED (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING. STATE CORPORATION COMMISSION

DATE 6-3-99

SIGNED

Michael Maier/MP (TECHNICIAN)

FORM CP-2/3

INV. NO. 60998

MAY 26 1999

5-26-99

CONSERVATION DIVISION Wichita, Kansas