

3-23-88

1 051025

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,088-0000
50' S of
E/2 E/2 NE, SEC. 4, T 22 S, R 16 W/8
3910 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4597

Lease Name Otte "A" Well # 1

Operator: Migwis

County Pawnee 125.00

Name & Address RR #4, Box 173AA

Well Total Depth 3846 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 979

Abandoned Oil Well Gas Well _____ Input Well _____ SHD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 23 Month: 3 Year: 19 88

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 3844' PBDT 3650' Perfs at 3587-91'

1st plug sand back to 3525' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 5 sx hulls and 125 sx ATL down 8 5/8".

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10 a.m. Day: 23 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3525' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 5 sx hulls and 125 sx ATL cement down the 8 5/8".

3-28-88

Maximum pressure 600 psi and shut in 500 psi.

Remarks: Used ATL cement by Allied. Recovered 2600' of 5 1/2" casing
(If additional description is necessary, use BACK of this report.)

RECEIVED
STATE CORPORATION COMMISSION

MAR 28 1988

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

(If additional description is necessary, use BACK of this report.) observe this plugging.

Signed Richard W. Long
(TECHNICIAN)

DATE 3-29-88

INV. NO. 20250