

1 040535

5-7

API NUMBER 19-145-20,712-0000

53

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C E/2 E/2 NW, SEC. 33, T 22 S, R 15 W/R

3960 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30457

Lease Name Oswald Well # 1

Operator: T-Bar Exploration, Inc.

County Pawnee 131.30

Name & Address 206 Wellington

Well Total Depth 4040 feet

Enid, OK 73703

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 259

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:45 p.m. Day: 7 Month: 5 Year: 19 91

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4000' with 150 sx cement, Perfs at 3739-46'

1st plug sand back to 3690' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 p.m. Day: 7 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 3680' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 350 psi and shut in 0 psi.

Well went on slight vacuum.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2141' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

I (did ~~not~~) observe this plugging.

Signed *Stephan J. Pfeiffer* (TECHNICIAN)

DATE 5-16-91
INV. NO. 31820

RECEIVED
STATE CORPORATION COM
5-14-91
MAY 14 1991

CONSERVATION DIVISI
Wichita, Kansas