

1080078

15-185-20626-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Not Available

NW 1/4, Sec. 4, T 23 S, R 12 W/EK

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6393

Lease Name Witt Well # 1

Operator: Brougner Oil, Inc.

County Stafford

Name & P. O. Drawer 1367

Address Great Bend, KS 67530

Well Total Depth 3710 feet 120.57

Conductor Pipe: Size _____ feet _____

Surface Casing: Size 8 5/8 feet 237

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 8:30 am Day: 25 Month: January Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Neal Peddicorn

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2 set at 3706' PBTD 3500 Perfs 3480 to 84. Sand back to 3430. Pump

5 sx cement with bailer. Recovered 2600' Squeezed well with 3 sx hulls, 20 sx gel,

50 sx cement, 5 sx gel, 1 sack hulls and released 8 5/8" plug followed with 100 sx

cement.

Signed J. R. Muf
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part _____ None _____

Operations Completed: Hour: 10:30 am Day: 25 Month: January Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2 set at 3706" PBTD 3500' Perfs 3480 to 84. Sand back to 3430

Pump 5 sx cement with bailer. Recovered 2600' Squeezed well with 3 sx hulls,

20 sx gel, 50 sx cement, 5 sx gel, 1 sack hulls and released 8 5/8" plug and

followed with 100 sx cement.

Remarks: Use 60/40 Pozmix, 2% gel, 3% cc. by Halliburton.

RECEIVED
STATE CORPORATION COMMISSION
FEB 02 1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as here stated
and that I (did / ~~was~~) observe this plugging.

INVOICED
DATE 2-3-84
NO. 0036

Signed J. R. Muf
(TECHNICIAN)