

1051299

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 19-Drill Completion Date 12/21/83

C NE, SEC. 8, T 22 S, R 22 W/E

3960 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6284

Lease Name Miller Estate Well # 8

Operator: VonFeldt Oil Operations

County Hodgeman 148.69

Name & Address Box 611

Well Total Depth 4575 feet

Russell, KS 67665

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 643

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 2 p.m. Day: 8 Month: 5 Year: 19 90

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 5 1/2" at 4573' Perfs at 4494-97, 4502-04' Elevation 2269' GL

1st plug pump 30 sx common cement and displace to 4100',

2nd plug pump 4 sx hulls, 5 sx gel, 60 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 155 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:50 p.m. Day: 8 Month: 5 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 30 sx common cement and displaced to 4100',

2nd plug pumped 4 sx hulls, 5 sx gel, 60 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 155 sx cement.

Maximum pressure 700 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan! Recovered 1068' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
I hereby certify that I have observed this plugging.

DATE 5-16-90

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 28178

5-11-90