

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-083-30008-00-00  
Spot: CNWSENW Sec/Twnshp/Rge: 8-22S-22W  
3630 feet from S Section Line, 3630 feet from E Section Line  
Lease/Unit Name: MILLER GUS Well Number: 8  
County: HODGEMAN Total Vertical Depth: 4544 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

Conductor Pipe: Size feet: 8 1/4 7.68  
Surface Casing: Size 8.625 feet: 268  
Production: Size 5.5 feet: 4527 WITH 125 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/13/2002 10:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO Phone: (316) 265-3311

Proposed Plugging Method: SAND TO 4320' & 4 SX CMT. PERFORATE AT 550' & PUMP 150 SX CMT. PRESSURE TEST. TIE ONTO BACKSIDE AND PUMP 100 SX CMT. PRESSURE TEST. TIE ONTO CASING AND PUMP 50 SX CMT. PRESSURE TEST.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 05/13/2002 11:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4527'. OPEN HOLE. SANDED TO 4320' THEN 4 SX CMT. PERFORATED AT 550' & PUMPED 150 SX CMT. MAXIMUM PRESSURE 600#. SHUT IN WITH 300#. TIED ONTO BACKSIDE AND PUMPED 100 SX CMT. PRESSURED TO 500# AND HELD. TIED ON TO CASING AND PUMPED 50 SX CMT. PRESSURED TO 300#. SHUT IN WITH 300#. CAME BACK LATER AND CHECKED CMT. CMT FELL TO 250'. PUMPED 30 SX CMT. STAYED FULL.

RECEIVED

MAY 17 2002

KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Michael Maier  
(TECHNICIAN)

INVOICED

MAY 14 2002

DATE 5-20-02

INV. NO. 2002061791

Karm