

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-083-10238-00-00  
Spot: CNWNW Sec/Twnshp/Rge: 8-22S-22W  
4620 feet from S Section Line, 4620 feet from E Section Line  
Lease/Unit Name: MILLER Well Number: 4  
County: HODGEMAN Total Vertical Depth: 4575 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

Conductor Pipe: Size feet: \$ 148.69  
Surface Casing: Size 8.625 feet: 246  
Production: Size 5.5 feet: 4563 WITH 100 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/13/2002 3:30 PM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO Phone: (316) 265-3311

Proposed Plugging Method: SAND TO 4350' & 4 SX CMT. PERFORATE AT 550' & PUMP 150 SX CMT. PRESSURE TEST. TIE ONTO BACKSIDE & PUMP 15 SX CMT. PRESSURE TEST. TIE ONTO CASING & PUMP 85 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 05/13/2002 4:20 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PBTD 4529'. PERFS AT 4484-94'. SANDED TO 4350' & 4 SX CMT ON TOP. PERFORATED AT 550' & PUMPED 150 SX CMT. MAXIMUM PRESSURE 300#. TIED ONTO BACKSIDE AND PUMPED 15 SX CMT. PRESSURED TO 500# AND HELD. TIED BACK ONTO CASING AND PUMPED 85 SX CMT, WAS ON VACUUM.

RECEIVED  
MAY 17 2002  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Michael Maier  
(TECHNICIAN)

INVOICED

MAY 14 2002

DATE 5-20-02

INV. NO. 2002061791

AP