

1 050578

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,254-0000

C W/2 SE NE, SEC. 18, T 22 S, R 11 ~~W/2~~

3300 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Lease Name Panning "A" Well # 1

Operator: L. D. Drilling, Inc.

County Stafford 119.02

Name & Address R. R. 1, Box 183B

Well Total Depth 3662 (Arbuckle) feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 345

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor L. D. Drilling, Inc. License Number 6039

Address R. R. 1, Box 183B, Great Bend, KS 67530

Company to plug at: Hour: 1:00 am Day: 24 Month: July Year: 19 85

Plugging proposal received from L. D. Davis

(company name) L. D. Drilling (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 554-574'

1st plug at 600' with 50 sx cement

2nd plug at 340' with 40 sx cement

3rd plug ^{solid bridge} hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:30 am Day: 24 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 600' with 50 sx cement; 2nd plug at 340' with 40 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton (if additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG 01 1985

INV. NO. 9264

AUG 26 1985

Signed Richard W. Lacey (TECHNICIAN)

7-26-85

CONSERVATION DIVISION WICHITA, KANSAS