

9-26

To: <sup>1</sup> 051090  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,475-0000

SW NW NE, SEC. 18, T 22 S, R 11 W/E

4290 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5107

Lease Name Panning Well # 2

Operator: H-30 Inc.

County Stafford 120.77

Name & Address 251 North Water

Well Total Depth 3716 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 260

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SHD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 8 a.m. Day: 26 Month: 9 Year: 19 88

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 5 1/2" at 3715' PBTB 3532' Perfs at 3314-3630' (4 sets) Elevation 1814' GL

1st plug sand back to 3260' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 11 a.m. Day: 26 Month: 9 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 3260' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 100 sx cement.

Maximum pressure 500 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2252' of 5 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED  
I ( ) did (not) observe this plugging.

Signed Richard W. Lacey (TECHNICIAN)

DATE 10-5-88

INV. NO. 22499