

1052329

TO: STATE CORPORATION COMMISSION

8-27

API NUMBER NA 15-185-22251-00-00
125' W SW SE SE SEC. 18, T 22 S, R 11 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1115 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME ALPERS WELL # 1A

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD

OPERATOR LICENSE # 6170

WELL TOTAL DEPTH 3700 FEET ^{120.25}

OPERATOR: GLOBE OPERATING, INC.

PRODUCTION CSG: SIZE 5 1/2" @ 3693' WITH 200 SX

NAME AND PO BOX 12

SURFACE CASING: SIZE 8 5/8" @ 339' WITH SX

ADDRESS GREAT BEND, KS 67530

ABANDONED OIL WELL GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 1:30 PM DAY: 27 MONTH: 08 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM MIKE KELSO

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

9-13-99

WERE: PERFS AT 3562-66

PLUG AT 600' WITH 5 SX GEL & 40 SX CEMENT. PLUG AT 350' WITH 50 SX CEMENT.

1999 SEP 13 1:28 PM
KANSAS CORP
NICE VEIL

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 4:15 PM DAY: 27 MONTH: 08 YEAR: 1999

ACTUAL PLUGGING REPORT

SANDED TO 3500' AND 5 SX CEMENT WITH A DUMP BAILER. SPOTTED PLUGS THROUGH CASING.

1ST PLUG AT 2127' WITH 50 SX CEMENT DISPLACED WITH 10 SX GEL. PLACED THIS PLUG DUE TO

GAS AND OIL FLOW. 2ND PLUG AT 600' WITH 5 SX GEL & 40 SX CEMENT.

3RD PLUG AT 350' WITH 50 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2715' OF 5 1/2" CASING.

IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

DATE 9-14-99

SIGNED Richard M. Lacey (TECHNICIAN)

FORM CP-2/3

INV. NO. 60518

INVOICED