

2 030242

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-079-20,384-0000

N 1/4 NE, SEC. 8, T 22 S, R 2, W 1/4

4060' feet from W/S section line

1320' feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9869

Lease Name Schrag Well # A#1

Operator: Chapman Energy of Okla. Inc.

County Harvey 106.44

Name & Address Sta. 320, 120 S. Market

Well Total Depth 3275' feet

Wichita, Ks. 67202

~~Production~~ Pipe: Size 5 1/2" feet 3274'

Surface Casing: Size 8 5/8" feet 267'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 5181

Address Box 176, Chase, Ks. 67524

Company to plug at: Hour: 13:00 Day: 26 Month: 4 Year: 19 85

Plugging proposal received from Clay Duntz

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: P.B.T.D. 3185' Perf. 3148' to 3162' Sand hole to 3100'
6 sq. cent., shoot & pull 5 1/2" casg. if high fluid pump
4 sq. hulls, 15 sq. gel, 100 sq. cent.

RECEIVED
STATE CORPORATION COMMISSION

7-3-85

Plugging Proposal Received by Duntz #2
CONSERVATION DIVISION (TECHNICIAN)
Wichita, Kansas

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 19:00 Day: 20 Month: 6 Year: 19 85

ACTUAL PLUGGING REPORT Sanded hole to 3100' dumped 6 sq. cent. with
bailer, shot and pulled 2201' 5 1/2" casg. Allied Cementing #813
pumped 400# hulls, 15 sq. gel, 100 sq. 60/40 Pasmoil 2% gel
down 8 5/8" sur. casg. Pump Press 300# S.I.P. 100#

Remarks: top plugging 6-25-85 ck top cent. app 10'
(If additional description is necessary, use BACK of this form.)

INVOICED

(I did, did not) observe this plugging.

DATE 6-10-85

Signed Don Thompson
(TECHNICIAN)

INV. NO. 8792