

1 050162

15.083-10223-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed 8-22-53

C NE SE, SEC. 17, T 22 S, R 22 W/X

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5331

Lease Name Ewy "A" Well # 4

Operator: Braden-Deem, Inc.

County Hodgeman

Name & Address Suite 1250, 125 North Market

Well Total Depth 4490 145.92 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 284

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 354, Chase, KS 67524

Company to plug at: Hour: 8:00 am Day: 29 Month: February Year: 19 84

Plugging proposal received from Bob Breneman

(company name) Kelso Casing Pulling (phone) 316-938-2467

were: 5 1/2 set at 4485 Squeezed 5 1/2" production casing at 3500', cement top at 2200' to 2500'

1st plug sand back to 4410 and dump 5 sx cement on top of sand

2nd plug squeeze through head with 3 sx hulls, 10 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls, and release 8 5/8" rubber plug and pump an additional 130 sx cement

Maximum pressure 500# shut-in pressure 200#

Plugging Proposal Received by Richard W. Lacy
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 10:00 am Day: 29 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2 set at 4485 Squeezed 5 1/2" production casing at 3500'

cement top at 2200' to 2500'

1st plug sand back to 4410' and dumped 5 sx cement on top of sand

2nd plug squeezed through head with 3 sx hulls, 10 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls, and released 8 5/8" rubber plug and pumped an additional 130 sx cement

Maximum pressure 500# and shut-in pressure 200#

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Allied #41332. Recovered 1516' of 8 5/8"
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

State Corporation Commission

Signed Richard W. Lacy
(TECHNICIAN)

DATE 3/7/84

MAR 07 1984

INV NO. 0559

CONSERVATION DIVISION

3-7-84